


PLAN VIEW SECTION


CONCRETE SLAB EXTERIOR STEEL FRAME @ CORNER DETAIL

SCALE: 1 1/2"=1'-0"




VIEW CONCRETE SLAB CONNECTION SECTION DETAIL BETWEEN MOD.

SCALE: 1 1/2"=1'-0"



RIGGING EMBEDDED ANCHOR DETAIL

S-1 SCALE: 1 1/2




TOP / SIDE RIGGING EMBEDDED ANCHOR DETAIL

SCALE: 1 1/2"=1'-0"

NOTES: (LIGHT WEIGHT CONCRETE)

1. ALL REBAR TO BE GRADE 60.
 2. ALL WELDABLE REINFORCEMENTS TO BE ASTM A706.
 3. CONCRETE STRENGTH TO BE 4000 PSI WITH SPECIAL ADDITIVE.
 4. MINIMUM CONCRETE COVER = 1 1/4" FOR #4 AND #5 BARS. TOP BARS MAY BE LOWER ONLY WHERE REQUIRED BY SPECIFIED SLOPES.
 5. PROVIDE (2) #5 BARS @ 8" O.C. TOP & BOTTOM AT PERIMETER OF EACH SLAB & PROVIDE (3) #5 BARS @ 8" O.C. TOP & BOTTOM AT EACH LIFTING LOCATION.
 6. TOP MAT: ADD TRIMMER BARS NEXT TO BLOCK OUTS IF CLEARANCE TO REGULAR LAYOUT IS GREATER THAN 2". TRIMMER BARS EXTEND 18" PAST OPENING, OR TERMINATE WITH 90° HOOK AND 8" EXTENSION. CENTER OF TRIMMER BARS TO BLOCK OUTS TO BE 2", TYP.
 7. SMALL BLOCK OUTS (8" x 8" MAX.) MAY BE ADDED AS REQUIRED FOR SERVICES. ADD TRIMMER BARS IF CLEARANCE TO REGULAR LAYOUT IS GREATER THAN 2".
 8. SPLICES: #4 BARS - 20" LAP
#5 BARS - 24" LAP
 9. PROTECT PIPE & FLOOR DRAINS THAT WILL BE ENCASED IN THE CONCRETE BY PROVIDING AN APPROVED WRAP.
 10. ONLY WHERE NOTED, IT IS ACCEPTABLE TO NOTCH HORIZONTAL LEG OF PERIMETER ANGLE.
 11. ALL EXPOSED FACES OF SLAB PERIMETER STEEL ANGLES SHALL RECEIVE GALVANIZING PAINT COATING.



CONCRETE SLAB & STEEL PERIMETER PLAN

SCALE: 1/2"=1'-0"



COPYRIGHT 2018, PUBLIC RESTROOM COMPANY THE MATERIAL IS THE EXCLUSIVE PROPERTY OF PUBLIC RESTROOM COMPANY AND SHALL NOT BE REPRODUCED, USED, OR DISCLOSED TO OTHERS EXCEPT AS AUTHORIZED BY THE WRITTEN PERMISSION OF PUBLIC RESTROOM COMPANY



PROJECT OWN

**LAND CONSERVANCY of SLO
San Luis Obispo County, CA**

PROJECT NAME AND LOCATION:
PISMO PRESERVE
LAND CONSERVANCY of
San Luis Obispo County,

SHEET TITLE:

**CONCRETE SLAB & STEEL
PERIMETER PLAN & DETAIL**

Drawn by:	NS / EVE	Job No.	10347
Checked by:	BB / CEK		
Current Date:	02/15/2018		
Start Date:	01/03/2018		S-1